

KERALA KERA KARSHAKA  
SAHAKARANA FEDERATION  
LIMITED NO.4370



Kerafed Coconut Complex, Mannankavu  
Naduvannur-673 614 , Kozhikode  
Tel: 0496 2933775  
E-mail: kerafedkccn2@gmail.com

Ref: KFD/KCC/QN/6/ 148

July 22, 2025

**INVITATION FOR QUOTATION: ANNUAL MAINTENANCE CONTRACT FOR  
50TON WEIGHBRIDGE**

Kerafed Coconut Complex Naduvannur Plant invites sealed quotations from experienced and reputed service providers for the Annual Maintenance Contract (AMC) of our 50 Ton Weighbridge. We are seeking a reliable partner to ensure the continuous and accurate operation of this critical equipment.

**Specification**

- Capacity : 50MT
- Indicator: ZM305 (IP69K).
- Load Cell: Analogue compression type (Loadcell T302 X 45 Ton).
- Platform Size : 9mtr × 3mtr.

**1. Scope of Work:**

The chosen service provider will be responsible for a comprehensive AMC, which includes:

- **Periodic Preventive Maintenance:** Regularly scheduled maintenance as per the weighbridge manufacturer's guidelines to ensure optimal performance, prevent potential breakdowns, and extend the lifespan of the equipment. This includes inspection, cleaning, lubrication, and minor adjustments. The contractor should commit to a minimum of **two scheduled preventive visits per quarter**.
- **On-Call Breakdown Services:** Prompt on-site support for any unexpected malfunctions or breakdowns. We require a guaranteed minimal response time to address issues quickly and minimize operational downtime. Please specify your assured response time in hours from the time of logging a service request.
- **Calibration Support:** Provision of necessary support for the periodic calibration of the weighbridge, ensuring its accuracy and compliance with relevant standards. While the calibration certificate may be arranged separately by KCCN, your role will involve facilitating the process and making necessary adjustments. Stamping Procedure: Include overhauling and preparation of machines for re-verification by W&I Inspectors in accordance with weights and measures act.
- **Replacement of Worn-Out or Defective Parts:** Identification and replacement of any parts that are worn out, defective, or nearing the end of their service life. The cost of such spares should be quoted separately from the AMC charges, either as an itemized list or based on a pre-agreed pricing structure.

Head Office: Kerala Kera Karshaka Sahakarana Federation No.4370 Kerafed Kera Towers,  
Water Works Compound, Vellayambalam, Vikas Bhavan Po , Thiruvananthapuram

Phone numbers : Plant manager- 6282431525, Deputy manager- 9020520797 ,  
Asst.manager( Finance)-94951 06941,Asst.manager(Stores)- 7907189105 Asst. manager ( Electrical)-79079 21691  
Official mail : kccn@kerafed.com, kccntech@kerafed.com, kccnfa@kerafed.com

## 2. Site Location:

The 50 Ton Weighbridge is located at: KERAFED Coconut Complex, Mannankavu, Naduvannur, Kozhikode – 673614, Kerala, India.

## 3. Terms & Conditions:

- **Contract Period:** The AMC will be valid for one year commencing from the date of the signed agreement.
- **Performance Guarantee:** The vendor must guarantee the proper functioning, accuracy, and calibration of the weighbridge throughout the entire AMC period.
- **Compliance & Safety:** All service activities must strictly adhere to relevant safety regulations, industry standards, and environmental compliance norms applicable in India. Service personnel must follow all KCCN site safety protocols.
- **Quotation Requirements:** Your sealed quotation must explicitly detail the following:
  - **Total Annual AMC Charges:** A consolidated figure for the entire one-year contract, excluding spare parts.
  - **Applicable Tax Components:** A clear breakdown of all taxes (e.g., GST) on the AMC charges.
  - **Number of scheduled preventive visits per quarter.**
  - **Guaranteed Response Time for Breakdowns:** State the maximum time (in hours) within which your technicians will arrive on-site after a breakdown call is logged.
  - **Exclusions or Additional Service Charges:** Clearly list any services or components not covered under the AMC, or any conditions under which additional charges might apply (e.g., services required outside of standard working hours, major overhauls not covered under AMC).
  - **Payment Terms:** Please specify your preferred payment schedule.
- **Submission Deadline:** The last date for the submission of sealed quotations is **2:00PM (IST) on July 28, 2025**. Quotations received after this time will not be considered. Quotations will be opened on the same day at **2.30 PM**.

## 4. Submission Details:

Please address your sealed quotation to: **The Plant Manager, Kerafed Coconut Complex Naduvannur.**

Ensure the sealed envelope is superscribed with: **"Quotation for 50 Ton Weighbridge AMC."**

## 5. Contact for Clarification:

For any site inspections or to seek further clarification regarding the scope of work or technical specifications, please contact us during business hours at: **0496 2933775, +91-9020520797**

KCCN reserves the right to accept or reject any or all quotations received without assigning any reason whatsoever. We look forward to your competitive proposals.

  
Plant Manager

KCCN

Plant Manager  
Kerafed Coconut Complex  
Mannankavu P.O, Naduvannur  
Kozhikode- 673-614  
Ph: 0496 2933775