KERALA KERAKARSHAKA
SAHAKARANA FEDERATION
LIMITED NO.4370

KERAFED
കേരാഫെഡ്

Kerafed Coconut Complex, Mannankavu
Naduvannur-673 614 , Kozhikode
Tel: 0496 2933775
E-mail: kccn @kerafed.com
kccnfa@kerafed.com
kccntech@kerafed.com
GST No: 32AAMAK9631N1Z3

KFD/KCCN/QN/2026/ 274 **16.11.2026**

QUOTATION NOTICE

Sub: Invitation of Quotations for Verification & Calibration of Six Storage Tanks – Reg.

Sealed quotations are invited from competent and technically qualified agencies for carrying out the verification and calibration of six vertical oil storage tanks installed at Kerafed Coconut Complex, Naduvannur, as per the applicable provisions of the Standards of Weights and Measures (General) Rules.

1. Details of Work

Sl.No.	Description	Quantity
1	Re-calibration of vertical storage tanks by strapping method	06 Nos.
2	Preparation of tank calibration/capacity charts	06 Nos.
3	Verification and stamping through the Legal Metrology Department, Kerala	06 Nos.

Tank Identification: A SERIES - A1, A2, A3(150MT each).
B SERIES - B1, B2, B3 (100MT each).

2. Scope of Work

The scope of work shall include:

1. Calibration of all six storage tanks by the strapping method.
2. Preparation of calibration charts incorporating deadwood correction, tilt correction, step-over correction and other applicable corrections.
3. Temperature correction in accordance with the applicable standards.
4. Preparation of calibration charts with dip increments of 1.0 cm and fraction charts with dip increments of 0.1 cm.
5. Coordination with the Legal Metrology Department for official verification and stamping.

3. Financial Details

The quotation shall clearly indicate:

- Agency's service charges for calibration and preparation of capacity charts.
- Applicable GST and other taxes, if any.
- Legal Metrology Department verification fee, separately.

The statutory verification fee payable to the Legal Metrology Department shall be borne by KCCN through e-Treasury, as applicable.

4. Terms and Conditions

1. The agency shall have the necessary technical competency and experience to undertake calibration of vertical storage tanks.
2. The work shall be carried out in accordance with the applicable statutory standards and Legal Metrology requirements.
3. The agency shall submit the completed calibration charts and relevant certificates upon completion of the work.
4. The agency shall coordinate with the Legal Metrology Department for verification and stamping.
5. The quoted rate shall clearly specify the applicable taxes and other charges.
6. KCCN reserves the right to accept or reject any or all quotations without assigning any reason.
7. Payment Terms:100% against satisfactory completion of work and on getting the certificate from the Legal Metrology.

5. Submission of Quotation

Interested agencies may submit their quotations in sealed covers superscribed **"Quotations for Verification & Calibration of Six Storage Tanks"** addressed to: **The Plant Manager**,Kerafed Coconut Complex, Mannankavu, Naduvannur, Kozhikode – 673614 or to to email id : kccn@kerafed.com , kccntech@kerafed.com.

Submission Deadline: The last date for the submission of sealed quotations is 1**:00PM (IST) on 24-11-2026**. Quotations received after this time will not be considered. Quotations will be opened on the same day at **2.30 PM.**

16/11/26

For **Plant Manager**
Kerafed Coconut Complex
Naduvannur